## **195 DCS** HEAT RECOVERY VENTILATOR

The cross-flow heat recovery cores transfer heat between two airstreams. The two cores are arranged for highly efficient counter-current airflow. They are easily removed for

Each airstream has an independent centrifugal blower driven by a common PSC motor,

## **ENGINEERING DATA:**

**MOTORS AND BLOWERS** 

ALUMINUM CORES



#### DEFROST

Damper defrost system.

#### CASE

20 gauge prepainted galvanized steel for superior corrosion resistance, insulated to prevent exterior condensation. Balancing ports are located on unit.

#### **DRAIN CONNECTION**

Two 1/2 in (12 mm) outer diameter.

#### ELECTRONICS

The DXPLO2 control included with the unit can be wall mounted in a central location of the home. 3 wire 20 gauge (min.) 100 ft. length (max.).

## with multiple fan speed operations.

#### FILTERS

cleaning

or service.

Washable MERV-6 air filters in exhaust and supply airstreams. Upgrade to MERV-13 option available.

THERMALLY CONDUCTIVE, PATENTED

#### MOUNTING

Threaded inserts at corners of the cabinet designed to accept the "S" hooks and hanging straps supplied with the unit.

## **OPTIONAL ACCESSORIES:**



#### Weather Hood 99-185 99-186 99-187



#### Terminator Fitting 99-TM4 99-TM5 99-TM6



#### LIFEBREATH CONTROL OPTIONS

		1	1	
FEATURES	99-DXPLO2	99-BCO2	99-BCO3	99-BCO4
5 speed fan operation on each mode	~			
2 speed fan operation (Low/High)		~		~
Continuous low speed fan operation	~	~	~	~
Humidity control through adjustable Dehumid- istat	~	~	~	
Large digital LCD screen	~			
LED status indicator lights		~	~	~
<b>Continuous Ventilation</b>	~	~	~	~
Continuous Recirculation*	~		~	
20 ON/40 OFF	~		~	~
10 ON/50 OFF	~			
20 ON/40 Recirculation*	~		~	~
20/40/60 min. High speed override button	~			
Compatible with 99-DETO2 Wireless Timer	~	~	~	~
3 wire connection	~	~	~	~

## TIMER OPTIONS

99-DET01 - 20/40/60 Minute Timer Initiates high speed ventilation for 20, 40 or 60 minutes. 3 wire connection.

#### 99-DETO2 - 20/40/60 Minute Timer

Initiates high speed ventilation for 20, 40 or 60 minutes. Wirelessly connects to main control for ease of installation. 40 ft approximate range.

#### 99-RXO2 - Wireless Repeater

Extends range of 99-DETO2 Wireless Timers. Plugs into 120V power outlet. Wirelessly connects to main control and 99-DETO2. Install at halfway point between timer and main wall control if timer is out of range.

INCLUDED WITH ALL MAX UNITS



99-DXPL02



99-DETO2 99-DETO1



\*Recirculation features not available on fan defrost models.

www.lifebreath.com

# **195 DCS** HEAT RECOVERY VENTILATOR


## PERFORMANCE (HVI CERTIFIED)

IN. W.G. (PA)	<b>0.2 (50)</b> CFM (L/s)	<b>0.3 (75)</b> CFM (L/s)	<b>0.4 (100)</b> CFM (L/s)	<b>0.5 (125)</b> CFM (L/s)	<b>0.6 (150)</b> CFM (L/s)	<b>0.7 (175)</b> CFM (L/s)	<b>0.8 (200)</b> CFM (L/s)	<b>0.9 (225)</b> CFM (L/s)
Net Supply Airflow	210 (99)	195 (92)	176 (83)	157 (74)	133 (63)	108 (51)	83 (39)	57 (27)
Gross Supply Airflow	220 (104)	203 (96)	184 (87)	163 (77)	140 (66)	114 (54)	87 (41)	59 (28)
Gross Exhaust Airflow	186 (88)	176 (83)	167 (79)	157 (74)	144 (68)	125 (59)	95 (45)	57 (27)

Sensible Effectiveness (ASE) @ 73 CFM (35 L/s)	32°F (0°C)	92%
Sensible Efficiency (SRE) @ 64 CFM (30 L/s)	32°F (0°C)	81%
Sensible Efficiency (SRE) @ 95 CFM (45 L/s)	32°F (0°C)	79%
Sensible Efficiency (SRE) @ 114 CFM (54 L/s)	-13°F (-25°C)	68%









ELECTRICAL SPECIFICATIONS			
VAC @ 60Hz	120		
Watts / Low Speed	74		
Watts / High Speed	123		
Amp Rating	1.5		

#### WEIGHT: 88 LBS (40 KG)

SHIPPING WEIGHT: 92 LBS (41.8 KG) .....

#### NOTE:

Front clearance of 25 in. (635 mm) is recommended for servicing unit. Outside ports, 6 in. (150 mm). Inside ports, 7 in. (178 mm).

MERV 13 Upgrade: 65-195-6R

## DIMENSIONS

DOOR SIDE VIEW SIDE VIEW Removable Heat Motor Recovery Airflow: Core ∕⊉ 18.75 in. (476 mm) ec > Stale Air to Outside 6 in. (150 mm) Collars 🔹 Fresh Air from Outside 7 in. (178 mm) Collars Stale Air from Inside Fresh Air to Inside ÷ Filters Blower 49 in. (1,245 mm) Defrost ŵ Condensate Damper 14.75 in. (375 mm) Drains **Defrost Air** From Inside WARRANTY Date: Contractor: Units carry a lifetime warranty on the HRV core and a 5 year Tag: \_ Supplier: \_ replacement parts warranty. All units conform to CSA and UL standards \_\_\_\_\_ Qty: \_\_\_ Project:\_\_\_ Quote #: \_ Engineer:\_ Submitted By: \_\_\_\_ Control: \_ Timer: \_\_\_\_\_\_ Timer Qty: \_\_ Indoor Air Systems www.lifebreath.com

69-195 DCS (0921) EN